Title

RMB Chivenor Firing Range Fencing

General Scope:

Remove existing firing range perimeter timber fencing & concrete posts. Supply & install new concrete posts, 1.4m high out of the ground as per the JSP. Supply & install new chain-link fence and extend 600mm below ground level to keep out local wildlife. Supply & install new pedestrian & vehicle access gates.

Works included:

- Mechanical excavation of existing fence posts & foundations.
- Mechanical excavation of trench, approx. 600mm below ground level.
- Exposure of services located within excavated trench.
- Level & set new concrete posts 1.4m above ground.
- Supply & install rolls of green powdercoated chain-link fence, 600mm below ground level & 1.4m above ground level.
- Install new pedestrian & vehicle gate, cladded with powder-coated green chainlink.
- Backfill trench & finish with stone chippings.

Duration:

1 Week

Client:

Dodd Group

Value: £30,000.00

Innovation:

- Full Utility and GPR Survey of site PAS 128 B
- Hand dig and Expose services prior to excavations PAS 128 A

Existing Fence Line RMB Chivenor





Removal of Fence Posts



large, Deep post Foundations





Excavation of trench for new fence line



Fence posts placed in excavation





Completion of Fence



Completed Fence







For more information contact:

Lee Probert – Managing Director 01275 545 290 enquires@benchmarkpm.co.uk www.benchmarkpm.co.uk

